


STATE ROAD #7
(200' R/W Per FDOT MAP 86100-2532)



(FRONTAGE ROAD)

AMERICA'S TOP TEAM



NOTE:
1. EXISTING ATT WATER MAIN CONNECTION UNDER DRY RETENTION AREA TO BE RE-ROUTED AND CONNECTED TO HAMPTON INN'S SYSTEM.

NOTE:
1. NO VALVES, METERS, FIRE HYDRANTS, CLEANOUTS, OR OTHER UTILITY APPURTENANCES ARE TO BE PLACED IN, OR ADJACENT TO, SIDEWALKS, CURBS, PARKING SPACES OR OTHER SUCH SITE FEATURES SO AS TO PRESENT A HAZARD OR RESTRICT THE MAINTENANCE OR OPERATION OF THE UTILITY INFRASTRUCTURE.
2. ALL PROPOSED ELEVATIONS ARE IN N.A.V.D.(88)
3. ALL VALVES, MANHOLES, CLEAN-OUTS, METER BOXES TO BE ADJUSTED TO GRADE TO GRADE PRIOR TO FINAL LIFT OF ASPHALT.
4. MINIMUM COVER ON ALL DIP WATER MAIN SHALL BE 30".
5. ALL SANITARY SEWER MAINS SHALL BE 8" PVC SDR-26 OR APPROVED EQUAL.
6. ALL CLEANOUTS SHALL BE USF 7635 SEWER VALVE & COVER SERIES.
7. ALL EXISTING VALVES SHALL BE RESTRAINED PRIOR TO ANY EXCAVATION/TIE-IN.



anderson
architecture, inc.

399 CAMINO GARDENS BLVD.
SUITE 202
BOCA RATON, FLORIDA 33432
V: 561.382.0220
www.andersonarchitecture.com

**SUN
TECH**
Sun-Tech
Engineering, Inc.
Engineers - Planners - Surveyors
1600 West Oakland Park Boulevard
Ft. Lauderdale, FL 33311
www.suntecheng.com
Phone: (954)777-5123 Fax: (954)777-3114
Certificate of Auth. # 7097

May 02 2016
CLIFFORD R. LOUTAN, P.E.
FL. REG. NO. 56890

A Site Plan Approval for:
**RESIDENCE INN
BY MARRIOTT**
State Road 7
Coconut Creek, Florida

REV	DATE	DESCRIPTION
1	5/2/16	REV PARKING

14-030
designed by ERIC ANDERSON
checked by CH

3744ws
date 02-23-15

SCHEMATIC
WATER &
SEWER
PLAN

C2

2 | C
AA 000197