

STORM SEWER
STRUCTURE SCHEDULE

BASIN & CB #	DRAINAGE AREA AC.	FRAME #	GRATE #	RIM	INVERT			
					NORTH	SOUTH	EAST	WEST
1	0.331	4160	6210	15.50				12.00
AS-BUILT								
2	0.286	4160	6210	16.00		12.50		
AS-BUILT								
3	0.331	4160	6210	15.50		12.00	12.00	12.00
AS-BUILT								
4	0.389	4160	6210	15.65				12.00
AS-BUILT								
5	0.390	4160	6210	15.65	12.00	12.00	12.00	
AS-BUILT								
6	0.184	4160	6210	16.00			12.50	
AS-BUILT								
SDMH 7	NA	USF-105M	6210	16.15		12.25		12.25
AS-BUILT								
8	0.386	4160	6210	15.50	12.00		12.00	
AS-BUILT								
9	0.292	4160	6210	15.50	12.00		8.10	12.00
AS-BUILT								
10	0.293	4160	6210	15.50			7.55	7.95
AS-BUILT								
11	0.430	4160	6210	15.50			7.45	7.45
AS-BUILT								
12	0.337	4160	6210	16.00		12.50		
AS-BUILT								
13	0.188	4160	6210	16.00	12.25	12.25		
AS-BUILT								
SDMH 14	NA	USF-105M	6210	17.25	12.00	7.40		7.40
AS-BUILT								
15	0.211	4160	6210	16.00		12.50		
AS-BUILT								
16	0.285	4160	6210	16.00		12.00	12.25	
AS-BUILT								
CS 17	NA	SEE	DETAIL	17.00	7.25	8.00		12.00
AS-BUILT								
SDMH 101	NA	USF-105M	6210	17.25			6.00	6.00
AS-BUILT								

GENERAL NOTES

- DRAINAGE RUNS ARE MEASURED TO CENTER OF STRUCTURE.
- THE MINIMUM FINISHED FLOOR ELEVATION IS 17.00.
- SEE PLAN FOR DESIGN ELEVATIONS.
- THE MINIMUM CROWN OF THE ROAD ELEVATION IS 15.50.
- SEE PLAN FOR DESIGN ELEVATIONS.
- DENSITY TESTS SHALL BE PERFORMED BY A CERTIFIED GEOTECHNICAL ENGINEERING FIRM DURING INSTALLATION OF THE DRAINAGE STRUCTURES. PIPE, ROAD SUBGRADE AND BASE. THE CITY OF COCONUT CREEK INSPECTOR MUST BE PRESENT DURING ALL DENSITIES.

CITY OF COCONUT CREEK EROSION & POLLUTION CONTROL NOTES

- PROVIDE TREE PROTECTION OF ALL SITE TREES TO REMAIN. TREE PROTECTION PER CITY OF COCONUT CREEK STANDARD DETAIL. CONTRACTOR TO OBTAIN DETAIL FROM CITY ENGINEER.
- PROVIDE FOR WEEKLY INSPECTION BY THE CONTRACTOR AND AFTER EVERY 0.25 INCH RAINFALL.
- PROVIDE AND LOCATE RAIN GAUGE ON SITE TO MEASURE RAINFALL ACTIVITY.
- ALL EROSION CONTROL MEASURES MUST MEET ALL THE REQUIREMENTS OF THE CITY OF COCONUT CREEK EROSION AND CONTROL PROCEDURES AND THE FLORIDA STORMWATER, EROSION AND SEDIMENT CONTROL INSPECTOR'S MANUAL.
- ALL EROSION AND SEDIMENT CONTROL MEASURES AND BMPs MUST BE MAINTAINED AS REQUIRED BY THE CITY FOR THE DURATION OF THE PROJECT.
- LOG BOOK OF ALL EROSION CONTROL INSPECTIONS MUST BE KEPT AND MAINTAINED ON-SITE.
- SPILL RESPONSE EQUIPMENT MUST BE ON-SITE AT ALL TIMES.

EROSION & POLLUTION CONTROL NOTES

- PRIOR TO ANY CONSTRUCTION, BALED HAY OR SILT SCREENS OR OTHER APPROVED SILT BARRIER SHALL BE INSTALLED BY THE EARTHWORK CONTRACTOR ALONG THE PROPERTY LINE AROUND ENTIRE SITE PERIMETER AND LIMITS OF CONSTRUCTION. SILT SCREENS SHALL REMAIN IN PLACE DURING THE LENGTH OF CONSTRUCTION OF THIS PROJECT (SEE DOT INDEX 102). IN ADDITION, SILT SCREENS OR BALED HAY MUST BE INSTALLED PER CITY OF COCONUT CREEK STANDARD DETAIL. CONTRACTOR TO OBTAIN DETAIL FROM CITY ENGINEER.
- DURING CONSTRUCTION, INLET SEDIMENT FILTERS SHALL REMAIN IN PLACE TO PREVENT THE RUNOFF OF SILT OR OTHER POLLUTANTS INTO THE DRAINAGE SYSTEM. (MIRAF) MAY BE USED FOR DITCH BOTTOM INLETS. SEE DETAIL SHEETS FOR CURB INLET SEDIMENT BARRIERS.
- ANY LOOSE SOIL LEAVING THE SITE MUST BE CLEANED FROM THE ADJACENT ROADWAY ON A DAILY BASIS.

CITY OF COCONUT CREEK PERMIT SET
MUST BE ON SITE AT ALL TIMES DURING CONSTRUCTION.
NOTICE INSPECTION REQUIRED
48 HRS. PRIOR TO COMMENCING ANY WORK IN THE PUBLIC RIGHT OF WAY CONTACT THE CITY OF COCONUT CREEK ENGINEERING DEPARTMENT FOR INSPECTION.

NOTE
APPROVAL OF THIS PLAN DOES NOT CONSTITUTE A PERMIT FOR CONSTRUCTION. A PERMIT FOR CONSTRUCTION MUST BE OBTAINED FROM THE CITY OF COCONUT CREEK ENGINEERING DEPARTMENT PRIOR TO COMMENCING CONSTRUCTION IN THE PUBLIC RIGHT OF WAY.

NOTICE TO CONTRACTOR
THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE, ON MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

48 HOURS BEFORE DIGGING
CALL SUNSHINE
TOLL FREE
1-800-432-4770
UNDERGROUND UTILITIES NOTIFICATION
CENTER OF FLORIDA

NOV 2, 2006
HOWARD A. BOYD, P.E. #47514 DATE

PROJECT: 5150 HILLSBORO	TITLE: POLLUTION PREVENTION PLAN, BASIN MAP, & DRAINAGE PLAN
DATE: 06/01/06	REVISIONS
SCALE: 1" = 40'	DATE COMMENTS
DRAWN BY: HEJ	09/15/06 REVISE PER SITE PLAN DRC COMMENTS
CHECKED BY: LJ	
APPROVED BY: HEJ	
PROJECT #: 06-0010	

AJ HYDRO ENGINEERING, INC. 5932 NW 73RD COURT PARKLAND, FL 33067 TEL (954) 344-7866 FAX (954) 344-7866	SHEET NUMBER PD1 OF 8
--	--------------------------------

