



*William Frank*  
 2/25/05

Bill Rosenberg FL LA #143  
 Ken Gardner FL LA #1569

DATE 2/25/05

REVISIONS

SCALE 1" = 20'-0"

SHEET IR-1

| KEY   | ITEM   | QTY.              |
|-------|--|-------------------|
| ————— | PVC laterals & mains shall be schedule 40 PVC (sized as shown on plans)                      | as required       |
| ===== | PVC sleeves shall be Schedule 40 PVC (sized 2 sizes larger than the pipe running through it) | as required       |
| ----- | TECHLINE by Netafim (209-453-6800), Model #: TLDL9-1201                                      | approx 3,000 l.f. |
|       | TECHFILTER by Netafim (209-453-6800), Model #: TF20912-2800                                  | 1                 |
|       | Netafim (209-453-6800) Pressure Regulators, Line Flushing Valves & Air/Vacuum Relief Valves  | as required       |
| WM    | 2" Water Meter & Backflow Preventer Assembly   | 1                 |
|       | 1 Station Controller that will provide up to 4 hour run times.                               | 1                 |
|       | MINI-Click II Rain Sensor (locate in area of free rainfall)                                  | 1                 |
| X     | RAINBIRD 200-PESP 2" Electromechanical Solenoid Control Valve                                | 1                 |
|       | Irrigation Control Wire  | as required       |
| ▲     | RAINBIRD Spray Heads 1800-SAM-PRS Series w/MPR nozzles 15-HQ                                 | 4                 |

