


BOTTOM COURSE 2.5" TYPE SP (12.5) (2 LIFTS) FRICTION COURSE 1" TYPE FC (12.5)

___10" LIMEROCK BASE (PRIMED)

---12" STABILIZED SUBGRADE (LBR 40)


3%



NW 51ST TERRACE

BCED REF#:

CONSTRUCTION SITE



4" DEEP' SWALE

SECTION I-I

NORTHERN CROSS SECTION

WITH PROPOSED RIGHT TURN LANE

48 HRS. PRIOR TO COMMENCING ANY WORK IN THE PUBLIC RIGHT OF WAY CONTACT THE CITY OF COCONUT CREEK ENGINEERING DEPARTMENT FOR INSPECTION.

LINE, AND BACKFILL TO THE REQUIRED SUBGRADE WITH CLEAN,

MAXIMUM DENSITY IN ACCCORDANCE WITH AASHTO T-99C

APPROVAL OF THIS PLAN DOES NOT CONSTITUTE A PERMIT FOR CONSTRUCTION. A PERMIT FOR CONSTRUCTION MUST BE OBTAINED FROM THE CITY OF COCONUT CREEK ENGINEERING DEPARTMENT PRIOR TO COMMENCING CONSTRUCTION IN THE PUBLIC RIGHT OF WAY.

48 HOURS BEFORE DIGGING
CALL SUNSHINE
TOLL FREE
<i>I-800-432-4770</i>
UNDERGROUND UTILITIES NOTIFICATION CENTER OF FLORIDA

HOWARD JABLON, P. E. #47514 DATE

TOPOGRAPHY NOTE: 1. ALL EXISTING AND PROPOSED ELEVATIONS ON THIS

PLAN ARE IN NAVD.

PROJECT: FBC OF CO	CONUT CREEK	TITLE: PAVING, GRADING, & DRAINAGE DETAILS
DATE: 07/15/14_	REVISIONS	AJ HYDRO SHEET
SCALE: NA	DATE COMMENTS	
DRAWN BY: HEJ	09-01-14 REVISED PER CITY SITE PLAN	
CHECKED BY: IJ	01-15-15 REVISE TRENCH / CS PER FIN	PARKLAND, FL 33067
APPROVED BY: HEJ		TEL (954) 344–7866
PROJECT #: 14-0050	-	FAX (954) 344–7866