

Table with columns: NO., SYM, COMMON NAME, BOTANICAL NAME, HEIGHT, SPREAD, DBH, CANOPY, STATUS, CANOPY LOSS S.F., COMMENTS. Contains detailed tree inventory data for Johnson Technology Park 2.

NOTES:

- 1. SEE SHEET L-1 FOR PROPOSED TREE AND PALM LOCATIONS.
2. THE CONTRACTOR SHALL REMOVE ALL TREES AND HEDGES AS PER PLANS AND AS APPROVED BY THE LOCAL GOVERNING AGENCIES (CITY OF COCONUT CREEK). TREE, PALM AND HEDGE MATERIAL SHALL INCLUDE ALL TRUNKS, STUMPS AND ROOTS. ALL EXCESS DEBRIS SHALL BE REMOVED FROM THE SITE AND DISPOSED OF AT AN APPROVED SITE. ALL HOLES AND DEPRESSIONS SHALL BE BACKFILLED WITH CLEAN, APPROVED BACKFILL.
3. LOCATIONS SHOWN FOR THE EXISTING TREES AND PALMS ARE APPROXIMATE. EXACT LOCATIONS ARE TO BE FIELD VERIFIED BY A REGISTERED LAND SURVEYOR (RLS) PRIOR TO ANY PAVING OR ANY OTHER SUCH WORK WHICH WILL BE IMPACTED BY ANY TREES OR PALMS TO REMAIN.
4. ALL INVASIVE EXOTIC VEGETATION AND ANY OTHER PLANTS LISTED AS CATEGORY 1, ON THE FLORIDA EXOTIC PEST PLANT COUNCIL'S LIST OF FLORIDA'S MOST INVASIVE SPECIES SHALL BE REMOVED FROM THE SITE AND MAINTENANCE SHALL GUARANTEE CONTROL OF RE-INVASION.
5. ALL TREES AND PALMS TO BE RELOCATED SHALL BE ROOT PRUNED AND CANOPY PRUNED ACCORDING TO ACCEPTED STANDARDS AS DEFINED BY THE NATIONAL ARBORIST ASSOCIATION, AND ALL PRE AND POST-TRANSPLANT OPERATIONS SHALL BE COORDINATED WITH UTMOST CARE TO MINIMIZE DAMAGE AND TRANSPLANT SHOCK. WATERING-IN AND WATERING SCHEDULES SHALL BE SUBMITTED TO THE PROJECT MANAGER FOR REVIEW AND APPROVAL PRIOR TO RELOCATION.

NOTES:

- 6. ALL TREES AND PALMS TO BE RELOCATED SHALL BE STAKED AND BRACED TO INSURE STABILITY AND MINIMIZE ROOT DAMAGE DURING THE PLANT ROOT RECOVERY PERIOD.
7. CONTRACTOR SHALL VERIFY WITH THE PROJECT SUPERINTENDENT THE PROPOSED LANDSCAPE AREAS PRIOR TO TREE AND PALM RELOCATION TO INSURE PROPER RELOCATION AND MINIMIZE ANY FIELD DISCREPANCIES WITH RESPECT TO PROPOSED PAVING, BUILDINGS, AMENITIES, ABOVE AND BELOW GROUND UTILITIES AND LIMITS OF PROPERTY.
8. CONTRACTOR SHALL ESTABLISH AN IRRIGATION SYSTEM TO PROVIDE FOR PRE AND POST-TRANSPLANT IRRIGATION SCHEDULING. TREE AND PALM FERTILIZATION SHALL BE ESTABLISHED CONCURRENTLY WITH IRRIGATION PRE AND POST-FERTILIZATION. THIS PROCEDURE SHALL BE CONDUCTED TO OPTIMIZE PLANT ESTABLISHMENT.
9. CONTRACTOR SHALL COORDINATE WITH THE PROJECT SUPERINTENDENT TO PLANT ALL RELOCATED TREES AND PALMS AT THE FINAL GRADE OF SITE.

TREE REMOVAL REPLACEMENT SCHEDULE

Table with columns: EXISTING TREE CANOPY, EXISTING TREES - TO REMOVE, REQUIRED TREE CANOPY MITIGATION, PROVIDED TREE CANOPY MITIGATION, PROPOSED TREE - PALM PLANTINGS - CATEGORY 1, CATEGORY 2, CATEGORY 3.

NOTES:


- 1. SEE LANDSCAPE PLANS FOR PROPOSED TREE AND PALM LOCATIONS.
2. THE CONTRACTOR SHALL REMOVE ALL TREES AND HEDGES AS PER PLANS AND AS APPROVED BY THE LOCAL GOVERNING AGENCIES (THE CITY OF COCONUT CREEK). TREE, PALM AND HEDGE MATERIAL SHALL INCLUDE TRUNKS, STUMPS AND ROOTS. ALL EXCESS DEBRIS SHALL BE REMOVED FROM THE SITE AND DISPOSED OF AT AN APPROVED SITE. ALL HOLES AND DEPRESSIONS SHALL BE BACKFILLED WITH CLEAN, APPROVED BACKFILL.
3. LOCATIONS SHOWN FOR THE EXISTING TREES AND PALMS ARE APPROXIMATE. EXACT LOCATIONS ARE TO BE FIELD VERIFIED BY A REGISTERED LAND SURVEYOR (RLS) PRIOR TO ANY PAVING OR ANY OTHER SUCH WORK WHICH WILL BE IMPACTED BY ANY TREES OR PALMS TO REMAIN.
4. ALL INVASIVE EXOTIC VEGETATION AND ANY OTHER PLANTS LISTED AS CATEGORY 1, ON THE FLORIDA EXOTIC PEST PLANT COUNCIL'S LIST OF FLORIDA'S MOST INVASIVE SPECIES SHALL BE REMOVED FROM THE SITE AND MAINTENANCE SHALL GUARANTEE CONTROL OF RE-INVASION.

A WRITTEN TREE REMOVAL PERMIT IS REQUIRED FROM THE CITY OF COCONUT CREEK PRIOR TO REMOVAL OF ANY TREES FROM THIS SITE.

SEE SHEET TD-1 FOR EXISTING TREE LOCATIONS, ETC.

SEE LANDSCAPE PLANS FOR PROPOSED LANDSCAPE PLANTINGS, LANDSCAPE LEGEND, SPECIFICATIONS, NOTES, DETAILS, ETC.

TREE DISPOSITION PLAN



DATE: Apr. 2016

SCALE: 1"=50'

DESIGNED BY: M.G.

DRAWN BY: M.A.S.

JOB NUMBER 13-3581

SHEET No. TD-2

SEAL

JAMES F. SACCH R.L.A. # 000192